VARIA CONNECT · REFERENCE

Construction Abbreviation List

Senarai Singkatan Pembinaan

361 abbreviations used on Malaysian construction sites, grouped into 12 areas, with English and Bahasa Malaysia meanings. Where one abbreviation has several meanings, the area is shown in brackets.

Areas: Safety & health · Authorities & approvals · Contracts & commercial · Project management · Design & drawings · Site operations & quality · Civil & structural · M&E services · Materials & testing · Plant & equipment · Environment · General & site terms

SAFETY & HEALTH (51)

Abbreviation	English	Bahasa Malaysia
AES	Authorised Entry Supervisor (confined space)	Penyelia Kemasukan Sah (ruang terkurung)
AESP	Authorised Entrant and Standby Person (confined space)	Pemasuk dan Pengawas Sedia Sah (ruang terkurung)
AGT	Authorised Gas Tester	Penguji Gas Sah
ALARP	As Low As Reasonably Practicable	Serendah yang praktikal
BBS	Behaviour-Based Safety	Keselamatan Berasaskan Tingkah Laku
CO	Carbon monoxide	Karbon monoksida
CPR	Cardiopulmonary Resuscitation	Resusitasi Kardiopulmonari
CSE	Confined Space Entry	Kemasukan Ruang Terkurung
EAP	Emergency Action Plan	Pelan Tindakan Kecemasan
ERP	Emergency Response Plan	Pelan Tindak Balas Kecemasan
ERT	Emergency Response Team	Pasukan Tindak Balas Kecemasan
FA	First Aid / First Aider	Pertolongan Cemas / Pemberi Pertolongan Cemas
FAC	First Aid Case	Kes Pertolongan Cemas
FAT	Fatality	Kematian
FRC	Fire-Resistant Clothing	Pakaian Kalis Api
H2S	Hydrogen sulphide	Hidrogen sulfida
HIRARC	Hazard Identification, Risk Assessment and Risk Control	Pengenalpastian Hazard, Penaksiran Risiko dan Kawalan Risiko
HSE / SHE	Health, Safety and Environment	Kesihatan, Keselamatan dan Alam Sekitar
IDLH	Immediately Dangerous to Life or Health	Bahaya Serta-merta kepada Nyawa atau Kesihatan
JHA	Job Hazard Analysis	Analisis Hazard Kerja
JSA	Job Safety Analysis	Analisis Keselamatan Kerja
LEL	Lower Explosive Limit	Had Letupan Bawah
LOTO	Lockout / Tagout	Kunci Keluar / Tag Keluar
LTA	Lost Time Accident	Kemalangan Hilang Masa Kerja
LTI	Lost Time Injury	Kecederaan Hilang Masa Kerja
LTIFR	Lost Time Injury Frequency Rate	Kadar Kekerapan Kecederaan Hilang Masa Kerja
MC	Medical Certificate (sick leave)	Sijil Cuti Sakit
MSDS / SDS	(Material) Safety Data Sheet	Helaian Data Keselamatan (Bahan)
MTC	Medical Treatment Case	Kes Rawatan Perubatan
NM	Near Miss	Nyaris Kemalangan
O2	Oxygen	Oksigen
OSH	Occupational Safety and Health	Keselamatan dan Kesihatan Pekerjaan
OSHMS	Occupational Safety and Health Management System	Sistem Pengurusan Keselamatan dan Kesihatan Pekerjaan
PEL	Permissible Exposure Limit	Had Pendedahan Dibenarkan
PFAS	Personal Fall Arrest System	Sistem Penahan Jatuh Diri
PPE	Personal Protective Equipment	Kelengkapan Perlindungan Diri (PPE)
PTW	Permit to Work	Permit Kerja

Abbreviation	English	Bahasa Malaysia
RPE	Respiratory Protective Equipment	Kelengkapan Perlindungan Pernafasan
SCBA	Self-Contained Breathing Apparatus	Alat Pernafasan Serba Lengkap
SHC	Safety and Health Committee	Jawatankuasa Keselamatan dan Kesihatan
SHO	Safety and Health Officer	Pegawai Keselamatan dan Kesihatan
SOP	Standard Operating Procedure	Prosedur Operasi Standard
SSS	Site Safety Supervisor	Penyelia Keselamatan Tapak
SWL	Safe Working Load	Beban Kerja Selamat
SWMS	Safe Work Method Statement	Pernyataan Kaedah Kerja Selamat
SWP	Safe Work Procedure	Prosedur Kerja Selamat
TBT / TBM	Toolbox Talk / Toolbox Meeting	Taklimat Keselamatan Harian
TRIR	Total Recordable Incident Rate	Kadar Jumlah Insiden Boleh Rekod
UA / UC	Unsafe Act / Unsafe Condition	Tindakan Tidak Selamat / Keadaan Tidak Selamat
WAH	Work at Height	Kerja di Tempat Tinggi
WLL	Working Load Limit	Had Beban Kerja

AUTHORITIES & APPROVALS (50)

Abbreviation	English	Bahasa Malaysia
BEM	Board of Engineers Malaysia	Lembaga Jurutera Malaysia
BOMBA / JBPM	Fire and Rescue Department of Malaysia	Jabatan Bomba dan Penyelamat Malaysia
BOWEC	Building Operations and Works of Engineering Construction (Safety) Regulations 1986	Peraturan Kendalian Bangunan dan Kerja Pembinaan Kejuruteraan (Keselamatan) 1986
BP	Building Plan approval	Kelulusan Pelan Bangunan
BQSM	Board of Quantity Surveyors Malaysia	Lembaga Juruukur Bahan Malaysia
CCC	Certificate of Completion and Compliance	Perakuan Siap dan Pematuhan
CF	Certificate of Fitness (Occupation) — replaced by CCC in 2007	Perakuan Layak Menduduki (digantikan oleh CCC)
CHRA	Chemical Health Risk Assessment	Penilaian Risiko Kesihatan Kimia
CIDB	Construction Industry Development Board	Lembaga Pembangunan Industri Pembinaan Malaysia
CIPAA	Construction Industry Payment and Adjudication Act 2012	Akta Pembayaran dan Adjudikasi Industri Pembinaan 2012
CIS	Construction Industry Standard (CIDB)	Standard Industri Pembinaan (CIDB)
DBKL	Kuala Lumpur City Hall	Dewan Bandaraya Kuala Lumpur
DO (planning)	Development Order (planning approval)	Kebenaran Merancang
DOE / JAS	Department of Environment	Jabatan Alam Sekitar
DOSH / JKKP	Department of Occupational Safety and Health	Jabatan Keselamatan dan Kesihatan Pekerjaan
EIA	Environmental Impact Assessment	Penilaian Kesan kepada Alam Sekeliling
EQA	Environmental Quality Act 1974	Akta Kualiti Alam Sekeliling 1974
FMA	Factories and Machinery Act 1967	Akta Kilang dan Jentera 1967
FOMEMA	Foreign Workers' Medical Examination Monitoring Agency	Agensi Pemantauan Pemeriksaan Perubatan Pekerja Asing
G1–G7	CIDB contractor grades by tender capacity (G7 = unlimited)	Gred kontraktor CIDB mengikut had tender (G7 = tiada had)
IWK	Indah Water Konsortium (national sewerage company)	Indah Water Konsortium (syarikat pembetungan negara)
JKR / PWD	Public Works Department	Jabatan Kerja Raya
JPS / DID	Department of Irrigation and Drainage	Jabatan Pengairan dan Saliran
JTK	Labour Department (Peninsular Malaysia)	Jabatan Tenaga Kerja Semenanjung Malaysia
LAM	Board of Architects Malaysia	Lembaga Arkitek Malaysia
MBSA / MBPJ	City councils (e.g. Shah Alam, Petaling Jaya)	Majlis Bandaraya (cth. Shah Alam, Petaling Jaya)
MS	Malaysian Standard	Standard Malaysia

Abbreviation	English	Bahasa Malaysia
NADOPOD	Notification of Accident, Dangerous Occurrence, Occupational Poisoning and Occupational Disease Regulations 2004	Peraturan Pemberitahuan Kemalangan, Kejadian Berbahaya, Keracunan Pekerjaan dan Penyakit Pekerjaan 2004
NIOSH	National Institute of Occupational Safety and Health (Malaysia)	Institut Keselamatan dan Kesihatan Pekerjaan Negara
OSC	One Stop Centre (local authority approvals)	Pusat Setempat
OSHA	Occupational Safety and Health Act 1994 (Act 514)	Akta Keselamatan dan Kesihatan Pekerjaan 1994 (Akta 514)
PAM	Malaysian Institute of Architects	Pertubuhan Akitek Malaysia
PBT / LA	Local Authority	Pihak Berkuasa Tempatan
PDPA	Personal Data Protection Act 2010	Akta Perlindungan Data Peribadi 2010
PERKESO / SOCSO	Social Security Organisation	Pertubuhan Keselamatan Sosial
PKK	Contractor Service Centre (government contractor registration)	Pusat Khidmat Kontraktor
PMA	Certificate of Fitness for lifting machinery (DOSH)	Perakuan Mesin Angkat
PMD	Certificate of Fitness for steam boilers (DOSH)	Perakuan Mesin Dandang
PMT	Certificate of Fitness for unfired pressure vessels (DOSH)	Perakuan Mesin Tekanan
PPK	Contractor Registration Certificate (CIDB)	Perakuan Pendaftaran Kontraktor
PSP	Principal Submitting Person	Orang Utama Yang Mengemukakan
QLASSIC	Quality Assessment System in Construction (CIS 7)	Sistem Penilaian Kualiti Kerja Pembinaan
SPAN	National Water Services Commission	Suruhanjaya Perkhidmatan Air Negara
SPKK	Government Contractor Certificate (CIDB)	Sijil Perolehan Kerja Kerajaan
SSM	Companies Commission of Malaysia	Suruhanjaya Syarikat Malaysia
ST	Energy Commission	Suruhanjaya Tenaga
TM	Telekom Malaysia	Telekom Malaysia
TNB	Tenaga Nasional Berhad (electricity utility)	Tenaga Nasional Berhad (utiliti elektrik)
UBBL	Uniform Building By-Laws 1984	Undang-Undang Kecil Bangunan Seragam 1984
USECHH	Use and Standard of Exposure of Chemicals Hazardous to Health Regulations 2000	Peraturan Penggunaan dan Standard Pendedahan Bahan Kimia Berbahaya kepada Kesihatan 2000

CONTRACTS & COMMERCIAL (46)

Abbreviation	English	Bahasa Malaysia
AI	Architect's Instruction	Arahan Arkitek
BC	Back-Charge	Caj Balik
BOQ / BQ	Bill of Quantities	Senarai Kuantiti
CA	Contract Administrator	Pentadbir Kontrak
CAR insurance	Contractor's All Risks insurance	Insurans Semua Risiko Kontraktor
CMGD	Certificate of Making Good Defects	Perakuan Pembaikan Kecacatan
CNC	Certificate of Non-Completion	Perakuan Kerja Tidak Siap
CPC	Certificate of Practical Completion	Perakuan Siap Kerja
CVI	Confirmation of Verbal Instruction	Pengesahan Arahan Lisan
D&B	Design and Build	Reka dan Bina
DLP	Defects Liability Period	Tempoh Tanggungan Kecacatan
DO	Delivery Order	Pesanan Penghantaran
EOT	Extension of Time	Lanjutan Masa
FA (account)	Final Account	Akaun Muktamad
GRN	Goods Received Note	Nota Penerimaan Barang
IC	Interim Certificate	Sijil Interim
IPC	Interim Payment Certificate	Sijil Bayaran Interim
L&E	Loss and Expense	Kerugian dan Perbelanjaan

Abbreviation	English	Bahasa Malaysia
LAD	Liquidated and Ascertained Damages	Ganti Rugi Tertentu dan Ditetapkan
LOA	Letter of Award	Surat Setuju Terima
LOI	Letter of Intent	Surat Niat
LS	Lump Sum	Harga Pukal
MR	Material Request	Permohonan Bahan
NSC	Nominated Subcontractor	Subkontraktor Dinamakan
NSS	Nominated Supplier	Pembekal Dinamakan
PB	Performance Bond	Bon Pelaksanaan
PC (claim)	Progress Claim	Tuntutan Kemajuan
PC Sum	Prime Cost Sum	Jumlah Kos Prima
PL	Public Liability insurance	Insurans Liabiliti Awam
PO	Purchase Order	Pesanan Belian
PS	Provisional Sum	Jumlah Peruntukan Sementara
PWD 203A	JKR standard form of contract (with quantities)	Borang kontrak standard JKR 203A (dengan kuantiti)
QS	Quantity Surveyor	Juruukur Bahan
RFP	Request for Proposal	Permintaan Cadangan
RFQ	Request for Quotation	Permintaan Sebut Harga
RM	Ringgit Malaysia	Ringgit Malaysia
RS	Retention Sum	Wang Tahanan
SC	Subcontract / Subcontractor	Subkontrak / Subkontraktor
SI	Site Instruction	Arahan Tapak
SMM2	Malaysian Standard Method of Measurement of Building Works, 2nd ed.	Kaedah Pengukuran Standard Kerja Bangunan, Edisi Ke-2
SO	Superintending Officer (JKR contracts)	Pegawai Penguasa
SOR	Schedule of Rates	Jadual Kadar
SST	Sales and Service Tax	Cukai Jualan dan Perkhidmatan
T&C (contract)	Terms and Conditions	Terma dan Syarat
VO	Variation Order	Arahan Perubahan Kerja
WC	Workmen's Compensation insurance	Insurans Pampasan Pekerja

PROJECT MANAGEMENT (23)

Abbreviation	English	Bahasa Malaysia
BIM	Building Information Modelling	Pemodelan Maklumat Bangunan
COW	Clerk of Works	Kerani Kerja
CPM	Critical Path Method	Kaedah Laluan Kritikal
EVM	Earned Value Management	Pengurusan Nilai Diperoleh
GC	General Contractor / Main Contractor	Kontraktor Utama
IBS	Industrialised Building System	Sistem Binaan Berindustri
KPI	Key Performance Indicator	Petunjuk Prestasi Utama
MOM	Minutes of Meeting	Minit Mesyuarat
MS (method)	Method Statement	Pernyataan Kaedah
NTP	Notice to Proceed	Notis untuk Memulakan
PD	Project Director	Pengarah Projek
PM	Project Manager	Pengurus Projek
PMC	Project Management Consultant	Perunding Pengurusan Projek
RACI	Responsible, Accountable, Consulted, Informed	Bertanggungjawab, Akauntabel, Dirujuk, Dimaklumkan
RE	Resident Engineer	Jurutera Residen
ROS	Required On Site (date)	Tarikh Diperlukan di Tapak
S-curve	Cumulative progress curve (planned vs actual)	Lengkung-S kemajuan kumulatif

Abbreviation	English	Bahasa Malaysia
SM	Site Manager	Pengurus Tapak
SOW	Scope of Work	Skop Kerja
SPM	Site Progress Meeting	Mesyuarat Kemajuan Tapak
TBC / TBA	To Be Confirmed / To Be Advised	Akan Disahkan / Akan Dimaklumkan
VE	Value Engineering	Kejuruteraan Nilai
WBS	Work Breakdown Structure	Struktur Pecahan Kerja

DESIGN & DRAWINGS (31)

Abbreviation	English	Bahasa Malaysia
ABD	As-Built Drawing	Lukisan Siap Bina
ARC	Architectural (drawing discipline)	Seni Bina
AWC	Approved With Comments	Diluluskan Dengan Komen
C&S	Civil and Structural	Awam dan Struktur
CAD	Computer-Aided Design	Reka Bentuk Berbantu Komputer
CL	Centre Line	Garis Tengah
DIA / Ø	Diameter	Diameter
DWG	Drawing	Lukisan
ELEV	Elevation	Pandangan Sisi
FA (drawing)	For Approval	Untuk Kelulusan
FFL	Finished Floor Level	Aras Lantai Siap
FGL	Finished Ground Level	Aras Tanah Siap
FI	For Information	Untuk Makluman
GA	General Arrangement (drawing)	Susun Atur Am
GL	Grid Line / Ground Level	Garisan Grid / Aras Tanah
IFC	Issued For Construction	Dikeluarkan Untuk Pembinaan
IFC (BIM)	Industry Foundation Classes (BIM file format)	Format fail BIM terbuka
LOD	Level of Development (BIM)	Tahap Pembangunan Model
MEP	Mechanical, Electrical and Plumbing	Mekanikal, Elektrikal dan Paip
NTS	Not To Scale	Tidak Mengikut Skala
RCP	Reflected Ceiling Plan	Pelan Siling Pantulan
REV	Revision	Semakan
RL	Reduced Level	Aras Laras
SD	Shop Drawing	Lukisan Kerja (Shop Drawing)
SECT	Section	Keratan
SS	Superseded	Digantikan
SSL	Structural Slab Level	Aras Papak Struktur
TOC	Top of Concrete	Aras Atas Konkrit
TOS	Top of Steel	Aras Atas Keluli
TYP	Typical	Tipikal
U/S	Underside	Bahagian Bawah

SITE OPERATIONS & QUALITY (22)

Abbreviation	English	Bahasa Malaysia
BM	Bench Mark	Tanda Aras
CAPA	Corrective and Preventive Action	Tindakan Pembetulan dan Pencegahan
CAR	Corrective Action Request	Permintaan Tindakan Pembetulan
DSR	Daily Site Report	Laporan Tapak Harian
HO	Handover	Serahan
ITP	Inspection and Test Plan	Pelan Pemeriksaan dan Ujian

Abbreviation	English	Bahasa Malaysia
MAS	Material Approval Submission	Penyerahan Kelulusan Bahan
MIR	Material Inspection Request	Permohonan Pemeriksaan Bahan
NCR	Non-Conformance Report	Laporan Ketakakuran
O&M	Operation and Maintenance (manual)	Operasi dan Penyelenggaraan
PDI	Pre-Delivery Inspection (before handover)	Pemeriksaan Sebelum Serahan
QA	Quality Assurance	Jaminan Kualiti
QC	Quality Control	Kawalan Kualiti
QMS	Quality Management System	Sistem Pengurusan Kualiti
QP	Quality Plan	Pelan Kualiti
RFA	Request for Approval / inspection	Permohonan Kelulusan / Pemeriksaan
RFI	Request for Information	Permintaan Maklumat
SIR	Site Inspection Report	Laporan Pemeriksaan Tapak
T&C (M&E)	Testing and Commissioning	Pengujian dan Pentauliahan
TBM	Temporary Bench Mark	Tanda Aras Sementara
VP	Vacant Possession	Milikan Kosong
WIR	Work Inspection Request	Permohonan Pemeriksaan Kerja

CIVIL & STRUCTURAL (29)

Abbreviation	English	Bahasa Malaysia
B/W	Both Ways (reinforcement)	Kedua-dua Arah
BP (pile)	Bored pile	Cerucuk Gerek
BRC	Welded steel mesh (from British Reinforced Concrete)	Jaring Keluli Kimpalan (BRC)
C/C	Centre to Centre	Pusat ke Pusat
CFA	Continuous Flight Auger (pile)	Cerucuk Auger Berterusan
COL	Column	Tiang
Cover	Concrete cover to reinforcement	Penutup Konkrit
DPC	Damp-Proof Course	Lapisan Kalis Lembap
DPM	Damp-Proof Membrane	Membran Kalis Lembap
EF	Each Face	Setiap Muka
ESCP	Erosion and Sediment Control Plan	Pelan Kawalan Hakisan dan Sedimen
FDN	Foundation	Asas
G25 / G30 / G40	Concrete grade (characteristic strength in N/mm²)	Gred konkrit (kekuatan ciri N/mm²)
GB	Ground Beam	Rasuk Bumi
MLT	Maintained Load Test (pile)	Ujian Beban Kekal
MP	Micropile	Cerucuk Mikro
PC (concrete)	Precast Concrete	Konkrit Pratuang
PDA	Pile Driving Analyser (dynamic pile test)	Penganalisis Pemacuan Cerucuk
PT	Post-Tensioned / Post-Tensioning	Pasca-Tegangan
R-bar	Plain round mild steel bar	Bar Keluli Lembut Bulat
RC	Reinforced Concrete	Konkrit Bertetulang
RW	Retaining Wall	Tembok Penahan
SFRC	Steel-Fibre Reinforced Concrete	Konkrit Bertetulang Gentian Keluli
SI (soil)	Soil Investigation	Penyiasatan Tanah
SOG	Slab on Ground	Papak Atas Tanah
SPT	Standard Penetration Test	Ujian Penusukan Piawai
SWD	Surface Water Drainage	Saliran Air Permukaan
T&B	Top and Bottom	Atas dan Bawah
Y-bar / T-bar	High-yield deformed reinforcement bar	Bar Tetulang Berubah Bentuk Kekuatan Tinggi

M&E SERVICES (34)

Abbreviation	English	Bahasa Malaysia
ACB	Air Circuit Breaker	Pemutus Litar Udara
ACMV	Air Conditioning and Mechanical Ventilation	Penyamanan Udara dan Pengudaraan Mekanikal
ACS	Access Control System	Sistem Kawalan Akses
AHU	Air Handling Unit	Unit Pengendalian Udara
AP	Wi-Fi Access Point	Titik Capaian Wi-Fi
ATS	Automatic Transfer Switch	Suis Pindah Automatik
BAS / BMS	Building Automation / Management System	Sistem Automasi / Pengurusan Bangunan
CCTV	Closed-Circuit Television	Televisyen Litar Tertutup
CW / HW	Cold Water / Hot Water	Air Sejuk / Air Panas
DB	Distribution Board	Papan Agihan
ELCB / RCCB	Earth Leakage / Residual Current Circuit Breaker	Pemutus Litar Bocor ke Bumi / Arus Baki
ELV	Extra-Low Voltage systems (data, CCTV, access)	Sistem Voltan Amat Rendah
FAS	Fire Alarm System	Sistem Penggera Kebakaran
FCU	Fan Coil Unit	Unit Gegelung Kipas
FHR	Fire Hose Reel	Gegelung Hos Bomba
GI	Galvanised Iron (pipe)	Besi Tergalvani
GT	Grease Trap	Perangkap Gris
HDPE	High-Density Polyethylene (pipe)	Polietilena Berketumpatan Tinggi
HV / LV	High Voltage / Low Voltage	Voltan Tinggi / Voltan Rendah
IC (sewer)	Inspection Chamber	Kebuk Pemeriksaan
MCB	Miniature Circuit Breaker	Pemutus Litar Kecil
MCCB	Moulded Case Circuit Breaker	Pemutus Litar Bekas Teracu
MDF	Main Distribution Frame (telecom)	Bingkai Agihan Utama
MH	Manhole	Lurang
MSB	Main Switchboard	Papan Suis Utama
PA	Public Address system	Sistem Siaraya
PPR	Polypropylene Random (pipe)	Paip Polipropilena
RWDP	Rainwater Downpipe	Paip Turun Air Hujan
SP / WP	Soil Pipe / Waste Pipe	Paip Najis / Paip Air Sisa
SSB	Sub-Switchboard	Papan Suis Kecil
TNB S/S	TNB substation	Pencawang Elektrik TNB
UPS	Uninterruptible Power Supply	Bekalan Kuasa Tanpa Gangguan
uPVC	Unplasticised Polyvinyl Chloride (pipe)	PVC Tanpa Pemplastik
VRF / VRV	Variable Refrigerant Flow / Volume (air-con)	Aliran Penyejuk Boleh Ubah

MATERIALS & TESTING (24)

Abbreviation	English	Bahasa Malaysia
AAC	Autoclaved Aerated Concrete (block)	Blok Konkrit Berudara Autoklaf
ACP	Aluminium Composite Panel	Panel Komposit Aluminium
CBR	California Bearing Ratio	Nisbah Galas California
CMU	Concrete Masonry Unit	Unit Batu Konkrit
COA / COC	Certificate of Analysis / Conformity	Sijil Analisis / Pematuhan
Cube test	Concrete cube compressive strength test (7 & 28 days)	Ujian Kekuatan Kiub Konkrit
FDT	Field Density Test (soil compaction)	Ujian Ketumpatan Lapangan
FRL	Fire Resistance Level / Rating	Tahap Rintangan Api
GFRC	Glass-Fibre Reinforced Concrete	Konkrit Bertetulang Gentian Kaca
GGBS	Ground Granulated Blast-furnace Slag	Sanga Relau Bagas
GRP	Glass-Reinforced Plastic	Plastik Bertetulang Kaca

Abbreviation	English	Bahasa Malaysia
MDD	Maximum Dry Density	Ketumpatan Kering Maksimum
MS (steel)	Mild Steel	Keluli Lembut
MTC (mill)	Mill Test Certificate	Sijil Ujian Kilang
NDT	Non-Destructive Testing	Ujian Tanpa Musnah
OPC	Ordinary Portland Cement	Simen Portland Biasa
PFA	Pulverised Fuel Ash (fly ash)	Abu Terbang
PLT	Plate Load Test	Ujian Beban Plat
RMC	Ready-Mixed Concrete	Konkrit Siap Bancuh
SIRIM	SIRIM Berhad (standards & product certification)	SIRIM Berhad (pensijilan produk)
Slump	Slump test (concrete workability)	Ujian Penurunan
SS (steel)	Stainless Steel	Keluli Tahan Karat
UPV	Ultrasonic Pulse Velocity (test)	Halaju Denyut Ultrasonik
W/C	Water–Cement ratio	Nisbah Air–Simen

PLANT & EQUIPMENT (17)

Abbreviation	English	Bahasa Malaysia
BH	Backhoe loader	Jengkaut Belakang
CAT scan	Cable Avoidance Tool scan (underground services)	Imbasan Pengesan Kabel Bawah Tanah
CP	Concrete Pump	Pam Konkrit
DT	Dump Truck / Tipper	Lori Tipar
EWP	Elevating Work Platform	Platform Kerja Boleh Naik
EX	Excavator	Jengkaut
GPR	Ground Penetrating Radar	Radar Penembusan Bumi
GS / Genset	Generator Set	Set Penjana
LMI	Load Moment Indicator	Penunjuk Momen Beban
MC (crane)	Mobile Crane	Kren Bergerak
MEWP	Mobile Elevating Work Platform	Platform Kerja Boleh Naik Bergerak
OEM	Original Equipment Manufacturer	Pengeluar Peralatan Asal
PH	Passenger Hoist	Lif Penumpang Binaan (Hoist)
PPM	Planned Preventive Maintenance	Penyelenggaraan Pencegahan Terancang
RT (crane)	Rough Terrain crane	Kren Rupa Bumi Kasar
SLI	Safe Load Indicator	Penunjuk Beban Selamat
TC	Tower Crane	Kren Menara

ENVIRONMENT (10)

Abbreviation	English	Bahasa Malaysia
BOD / COD	Biochemical / Chemical Oxygen Demand	Keperluan Oksigen Biokimia / Kimia
C&D waste	Construction and Demolition waste	Sisa Pembinaan dan Perobohan
dB(A)	A-weighted decibels (noise level)	Desibel berwajaran-A (paras bunyi)
EMP	Environmental Management Plan	Pelan Pengurusan Alam Sekitar
EMS	Environmental Management System	Sistem Pengurusan Alam Sekitar
LD-P2M2	Land-Disturbing Pollution Prevention and Mitigation Measures	Langkah Pencegahan dan Mitigasi Pencemaran Gangguan Tanah
PM10 / PM2.5	Particulate matter (dust) ≤10 / ≤2.5 µm	Habuk zarahan ≤10 / ≤2.5 µm
SW	Scheduled Waste	Buangan Terjadual
TSS	Total Suspended Solids	Jumlah Pepejal Terampai
WWTP / STP	Wastewater / Sewage Treatment Plant	Loji Rawatan Air Sisa / Kumbahan

GENERAL & SITE TERMS (24)

Abbreviation	English	Bahasa Malaysia
Approx.	Approximately	Lebih kurang
CIDB Green Card / PPB	Construction Personnel Registration card (CIDB)	Kad Hijau CIDB / Pendaftaran Personel Binaan
CLQ	Centralised Labour Quarters	Penginapan Pekerja Berpusat
ETA	Estimated Time of Arrival	Anggaran Masa Ketibaan
FYI	For Your Information	Untuk Makluman Anda
HQ / HO	Headquarters / Head Office	Ibu Pejabat
ID	Identification	Pengenalan
Kongsi	Workers' quarters on or near site	Rumah kongsi pekerja
Lm / m run	Linear metre	Meter larian
m² / m³	Square metre / cubic metre	Meter persegi / meter padu
N/A	Not Applicable	Tidak Berkaitan
nr / No.	Number (count, as used in BQ)	Bilangan
OT	Overtime	Kerja Lebih Masa
PIC	Person In Charge	Orang Bertanggungjawab
PLKS	Temporary Employment Visit Pass (foreign worker work permit)	Pas Lawatan Kerja Sementara
Prov.	Provisional	Sementara
QTY	Quantity	Kuantiti
S/C	Subcontractor	Subkontraktor
SPV	Supervisor	Penyelia
t	Tonne (1,000 kg)	Tan metrik
TBA	To Be Advised	Akan Dimaklumkan
TCP	Traffic Control Plan	Pelan Kawalan Trafik
TMP	Traffic Management Plan	Pelan Pengurusan Trafik
WIP	Work In Progress	Kerja Dalam Pelaksanaan

Draft list. Bahasa Malaysia terms are suggested translations; check official terms with the relevant authority before using them in contract documents.